



SPECIFICATION OF PRODUCT 承认书

CUSTOMER: _		
DESCRIPTION: _	Magnetic Buzzer	
FUSHENG P/N: _	FMB09A03	
CUSTOMER P/N: _		
DATE:	2018-8-28	

CUSTOMER	APPROVER	CHECKER
	Cui	Bing Yan

泰州福声电子科技有限公司

地址:江苏省泰州市海陵区凤凰西路 1688 号

电话: 0086-523-86219066 传真: 0086-523-81601108

邮箱: sales@electronic-tech.cn

网址: www.tzfsdz.com






1.SPECIFICATION 规格

No.	ltem	Unit	Specification	Condition
1	Oscillation Frequency	Hz	2700±300	
2	Operating Voltage	VDC	2~5	
3	Rated Voltage	VDC	3	
4	Current Consumption	mA	MAX. 30	at Rated Voltage
5	Sound Pressure Level	dB	MIN. 80	at 10cm at Rated Voltage
6	Operating Temperature	$^{\circ}$	-20~+70	
7	Storage Temperature	$^{\circ}$	-30 ~ +85	,
8	Dimension	mm	9 x H 5.5	See appearance drawing
9	Weight (MAX)	gram	1	
10	Housing Material		PPO(Black)	
11	Leading Pin		Tin Plated Brass(Sn)	See appearance drawing
12	Environmental Protection Regulation		RoHS	

2. APPEARANCE DRAWING 尺寸图



Tol: \pm 0.5 Unit: mm


3.TESTING METHOD

Standard Measurement conditions


Temperature:25±2°C Humidity:45-65%

Acoustic Characteristics:


The oscillation frequency, current consumption and sound pressure are measured by the measuring instruments shown below



In the measuring test, buzzer is placed as follows:




4. VOLTAGE / CURRENT / SOUND PRESSURE CHARACTERISTICS



5. Soldering Condition

(1)Recommendable reflow soldering condition is as follows (Reflow soldering is twice)

Note: It is requested that reflow soldering should be executed after heat of product goes down to normal.



Heat resistant line

(Used when heat resistant reliability test is performed)

(2)Manual soldering

Manual soldering temperature 350 °C within 5 sec.

6. RELIABILITY TEST

	NO.	ITEM	TEST CONDITION AND REQUIREMENT	
	1	High Temperature Test (Storage)	After being placed in a chamber with 85 2°C for 96 hours and then being placed in normal condition for 2 hours. Allowable variation of SPL after test: 10dB.	
	2	Low Temperature Test (Storage)	After being Placed in a chamber with -30 2°C for 96 hours and then being placed in normal condition for 2 hours. Allowable variation of SPL after test: 10dB.	
	3	Humidity Test	After being Placed in a chamber with 90-95% R.H. at 40 2°C for 96 hours and then being placed in normal condition for 2 hours. Allowable variation of SPL after test: 10dB.	
The part shall be subjected to 5 cycles. One cycle shall be consist +70°C		The part shall be subjected to 5 cycles. One cycle shall be consist of: +70°C		
>	4	Temperature Cycle Test	+25°C +25°C +25°C	
			Allowable variation of SPL after test: 10dB.	
	5	Drop Test	Drop on a hard wood board of 4cm thick, any directions ,6 times, at the height of 75cm. Allowable variation of SPL after test: 10dB.	
After being applied vibration of amplitude of band of vibration frequency to each of 3 perpertation applied vibration frequency to each of 3 perpertations.		Vibration Test		
	7	Solderability Test	Lead terminals are immersed in rosin for 5 seconds and then immersed in solder bath of +300 5°C for 3 1 seconds. 90% min. lead terminals shall be wet with solder (Except the edge of terminals).	
Terminal Strength Pulling Test The force of 9.8N(1.0kg) is applied to each terminal in at 10 seconds. No visible damage and cutting off.				

TEST CONDITION.


 Standard Test Condition
 : a) Temperature: +5 ~ +35℃
 b) Humidity: 45-85%
 c) Pressure: 860-1060mbar

 一般测试条件
 : a) 温度: +5 ~ +35℃
 b) 湿度: 45-85%
 c) 气压: 860-1060mbar

 Judgment Test Condition
 : a) Temperature: +25 ± 2℃
 b) Humidity: 60-70%
 c) Pressure: 860-1060mbar

 争议时测试条件
 : a) 温度: +25 ± 2℃
 b) 湿度: 60-70%
 c) 气压: 860-1060mbar

7. PACKING STANDARD 包装



Foam Tray	240mmx160mmx30mm	1x100PCS=100PCS
Plastic Bag		10x100PCS=1000PCS
Carton Box	520mmx420mmx280mm	5x1000PCS=5,000PCS